
2022

SALT CREEK LEVEE TRAIL RESURFACING LOWER PLATTE SOUTH NRD LINCOLN, NEBRASKA

PROJECT OFFICIALS:

MARK LIDEMANN AL LANGDALE ARIANA KENNEDY ROBERT BARTJA



INDEX OF SHEETS

SHEET 1: COVER

SHEET 2: LOCATION MAP, CONSTRUCTION NOTES, QUANTITIES


SHEET 3: TYPICAL DETAIL



2022 CREEK LEVEE TRAIL RESURF LOWER PLATTE SOUTH NRD

COVER SHEET





CONSTRUCTION NOTES:


2

■ Miles

- 1. THE ITEMS IDENTIFIED IN THE SCHEDULE OF APPROXIMATE QUANTITIES ARE INTENDED TO IDENTIFY THE MAJOR WORK ITEMS. ALL ITEMS NOTE SPECIFICALLY MENTIONED SHALL BE CONSIDERED SUBSIDIARY TO BID ITEMS TO WHICH THEY ARE RELATED AND WILL NOT BE CONSIDERED PAY ITEMS.
- 2. CONTRACTOR SHALL PROVIDE BARRICADES WITH 'SIDEWALK CLOSED' SIGNS AT EACH TRAIL ENTRANCE. THESE SHALL BE MAINTAINED THROUGHOUT THE PROJECT.
- 3. AGGREGATES USED SHALL MEET REQUIREMENTS AS STATED IN THE PLANS.
- 4. UPON COMPLETION OF SPREADING OPERATIONS, THE AGGREGATES SHALL BE THOROUGHLY COMPACTED. THE COMPACTION MAY BE TESTED IN ACCORDANCE WITH ASTM D 1556 OR ASTM D 2167 BY OWNER. COMPACTION SHALL BE DONE IN LIFTS NO THICKER THAN 5".
- 5. NO CRUSHED CONCRETE ALLOWED FOR SURFACING.

FOR INFORMATION ONLY SCHEDULE OF APPROXIMATE QUANTITIES			
Calvert to Van Dorn	5445	404	673
Van Dorn to South Street	1425	105	176
South Street to A Street	2595	192	320
A Street to Rosa Parks	2105	156	260
Rosa Parks to O Street	1465	109	181
O Street to Haymarket Park	2085	155	258





TYPICAL RESURFACING SECTION

NOTE: EXISTING TRAIL VERTICAL ALIGNMENT SHALL REMAIN THE SAME